


List of corrigendum


Tender document

| Sl. No | Ref. to Documents | Corrigendum particulars | |
|--------|--|---|--|
| | | Existing | Modified |
| 1 | Section-2 A. General 3. Qualification of the Tender 3.2 (c) Electrical | LED Street Light 150 Watts – 224 Nos. | This specification may be read as "LED Street Light – 224 Nos". |
| 2 | Section-2 A. General 3. Qualification of the Tender 3.2 (c) Electrical | LT UG Cable 1.1 KV – 12,800 RMT | This specification may be read as " UG Cable – 12,800 RMT ". |
| 3 | Section-2 F. Award of contract 29. Security deposit | 29.1 Within 20 days of Receipt of the Letter of Acceptance, the Successful Tenderer shall deliver to the Employer a Security Deposit in any of the Forms given below for an Amount equivalent to 10% of the Contract Price plus Additional Security for Unbalanced Tenders in accordance with Sub Clause 25.5 of ITT and Clause 43 of the Conditions of Contract. | The rate of performance security is specified as per original KW-4 29.1, however as per the Government order No: ಅಖ 456 ವೆಚ್ಚ-12/2022, ಬೆಂಗಳೂರು, ದಿ.10-08-2022, the rate of performance security will be modified at the time of issue of letter of acceptance to the successful tenderer. |



Superintending Engineer I/c
KSSIDC Ltd.,

Schedule-B

| Sl. No | Item code | Corrigendum particulars | | Reasons |
|--------|-----------|--|--|---|
| | | Existing | Modified | |
| 16 | 16 | Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement shall be paid separately) Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregates. As per the specification and directions of the Engineer in charge with all lead and lifts. approved estimated price Rs. 6228.20 | Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates. As per the specification and directions of the Engineer in charge with all lead and lifts. approved estimated price Rs. 6109.40 | Due to typographical error the M10 Concrete aggregate size is typed as 20mm instead of 40mm it has to be read as 40mm. Also the rate in the column of approved estimated price has to be read as Rs. 6,109.00 |


 Superintending Engineer I/c
 KSSIDC Ltd.,

| | | | | |
|----|----|--|---------------------------------------|---|
| 17 | 17 | approved estimated price Rs. 6982.80 | approved estimated price Rs. 6864.16 | Due to typographical error caused, the rate in the column of approved estimated price has to be read as Rs. 6864.16 |
| 18 | 18 | approved estimated price Rs. 6,959.70 | approved estimated price Rs. 6904.74 | Due to typographical error caused, the rate in the column of approved estimated price has to be read as Rs. 6904.74 |
| 19 | 19 | approved estimated price Rs. 6,977.30 | approved estimated price Rs. 7,286.89 | Due to typographical error caused, the rate in the column of approved estimated price has to be read as Rs. 7,286.89 |


 Superintending Engineer I/c
 KSSIDC Ltd.,